

PROPOSED DRAFT  
DECEMBER 2014

**409.03.10 Sweeping and Brooming**

**B. Final Sweeping and Brooming.** Perform final sweeping and brooming operations to remove excess loose material no sooner than 5 calendar days before final pavement markings, unless otherwise directed by the Project Manager. Provide traffic control in accordance with Section 618.

COMMENTS

1. I'd like the current Final Sweeping Specification to remain the same.

Response: The Department realizes this operation may not be necessary on every project. This change was made to ensure better coordination between the Contractor and Department when scheduling this work.

FINAL  
EFFECTIVE APRIL 16, 2015

**409.03.10 Sweeping and Brooming**

**B. Final Sweeping and Brooming.** Perform final sweeping and brooming operations to remove excess loose material no sooner than 5 calendar days before final pavement markings. Coordinate with the Project Manager to ensure Final Sweeping and Brooming is necessary. Provide traffic control in accordance with Section 618.